

NOTICE.

The undermentioned plant not required by this Division is for sale, and tenders for the purchase of the same per unit, will be received by undersigned up to 4th October, 1920:—

1. Two Babcock and Wilcox boilers.

Specification of each.

Length of drum	23 feet	Length of furnace	6 feet
Diameter of drum	3 "	Number of tubes	54
Width of furnace	3½ "	Diameter of tubes	4 inches

Mountings on each.

Stop valve.

Feed check valve.

Dead weight safety valve.

Gauge glass and fittings.

Blow off cock.

The above equipped with super-heaters with dampers, complete. Probable working steam pressure 60 to 70 lbs. square inch.

2. One Lancashire Boiler.

Specification.

Length of drum	30 feet	Diameter of drum	7½ feet
Width of furnace			2½ feet

Mountings.

Stop valve.

Feed check valve.

Dead weight safety valve.

Blow off cock.

All in good order working steam pressure 125 lbs. square inch.

3. One simple non-condensing Steam Engine with fly wheel on one side and belt pulley on the other.

Specification.

Capacity	3 H. P.	Cylinder diameter	7 inches
Working steam pressure	120 lbs. square inch.	Length of stroke	8 "

Ordinary slide valve arrangement. All in good order.

4. One Donkey Pump.

Diameter of cylinder	4½ inches	Diameter of plunger	2½ inches
Length of stroke	4 "	Suction and delivery	1½ "

All in working order.

5. One Air Compressor with Engine complete by Westing House Brake & Co., Ltd., No. 27983, London.

6. Shunt Wound Dynamo of 110 volt. and D. C. Further information of Dynamo not available.

Delivery.—At the Pumping Station, Soldevanhalli, on acceptance of one of the offers and payment of full value. Dis dismantlement by purchaser and removal outside of Engine Room or House will be under the supervision of the Superintendent in charge, whose instructions on the subject will have to be strictly followed by purchaser and in the event of the latter not conforming to the instructions, the Superintendent is empowered to stop the work and represent the matter to undersigned for his inspection of the work and further orders.

7. The plant is open to inspection on all days between 10 A.M. and 4 P.M. except Sundays, at Soldevanhalli Pumping Station.

8. Full value of the purchase money should be paid within one month from the date of acceptance of the tender.

G. V. RAO,
Executive Engineer.

BANGALORE DIVISION.

Notice dated 7th September 1920.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to 25th September 1920, for constructing a new Nagar-khaan and compound wall to the Akkalsha Khadri Durga at Channapatna. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1920.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred (Rs. 200) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a new Nagarkhana and compound wall to the Akkalsha Khadri Durga at Channapatna," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Tender with vague quotations, such as, "as per market rates," and so on will be rejected.

(Constructing a new Nagarkhana and compound wall to the Akkalsha Khadri Durga at Channapatna).

No.	Items of work.	Per	Quantity
1	Removing fallen structure and debris and filling basement and pit.	Lumpsum	
2	Excavating foundation	C. yd.	30
3	Burnt stone in mortar	C. ft.	808
4	Burnt brick in mortar (lower floor)	Do	596
5	Do (first floor)	Do	705
6	Cut stone work (beams)	Do	731
7	Burnt stone slabs 6" thick (1" dressing sides and top)	S. ft.	801
8	Pukka terracing 9" thick including plastering both sides	Sq.	3.62
9	Flooring with 3" concrete and plastered over	Do	3.14
10	Plastering with mortar (lower floor)	Do	11.42
11	Do (first floor)	Do	15.35
12	Pointing with cement	Do	9.01
13	Whitewashing (lower floor)	Do	21.25
14	Do (first floor)	Do	15.35
15	Teakwood windows panelled with iron bars, etc., complete	S. ft.	83
16	Teakwood work wrought and put up	C. ft.	54.06
17	Teakwood work gate with planking of 2" thick	S. ft.	144
18	Fixing iron kubs to gate shutters	Each	8
19	Cutting holes to bottom and top slab	Do	8
20	Teakwood staircase (3' wide $\times$ $\frac{1}{2}$ ' thick)	R. ft.	13
21	Wood oiling	Sq.	3.01
22	Chocolate painting	Do	3.98
23	Colourwashing	Do	1.80
24	Burnt brick coping including plastering	R. ft.	15
25	Cornice work 9" $\times$ 9"	R. ft.	96

T. S. RAGHAVACHAR,
Executive Engineer.

KOLAR DIVISION.

Dated 3rd September 1920.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 10th October, 1920, for constructing an Anglo-Vernacular School at Mulbagal. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1921.

2. The plans, detailed estimate and conditions, may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees five hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing an Anglo-Vernacular School at Mulbagal in default of which, tenders will be rejected."

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for constructing an Anglo-Vernacular School at Mulbagal.

No.	Items of work	Unit	Quantity
1	Earthwork excavation and filling basement	C. yd.	200
2	Metal Concrete in mortar	C. ft.	1461
3	Stone in mortar foundation and basement	Do	5512
4	Burnt brick in clay superstructure	Do	8205
5	Do in chunam do	Do	1299
6	Do do in arch work	Do	284
7	Burnt stone slabs dressed and fixed	S. ft.	892
8	Plastering in chunam	Sqr.	140-17
9	White and colour washing	Do	140-17
10	Teakwood pannelled door with iron fastings, etc., complete	S. ft.	480
11	Do windows with glazed shutters, iron bars, etc., complete,	Do	435
12	Do rectangular glazed	Do	96
13	Do circular do	Do	124
14	Silicate painting	S. qr.	24-65
15	Cut stone pillars 2 times dressed with base and capital, complete	No.	16
16	Brick masonry pillars with base and caps	No.	6
17	Teakwood work wrought and put up	C. ft.	249-60
18	Ridge tiles set in mortar and pointed	R. ft.	203
19	Roofing with 1st class Mangalore tiles with teak reapers, complete	Sqr.	53-17
20	Flooring with Cuddapah slabs for verandah, Mangalore tiles, for rooms over 3" concrete and cement pointed	Do	33-27
21	Chunam borders	R. ft.	112
22	Ionice entablature	Do	55
23	Cornice 12" thick	Do	500
24	Preparing Ionice and Doric capitals	No.	18
25	Do bases	Do	18
26	Moulded arch volts for arches	R. ft.	31
27	Preparing rectangular and circular pannels, ornamental flower works and circular complete	Lump sum	
28	Clearing site and levelling ground, etc., complete	Lump sum	
29	Teakwood ornamental eave board 1" thick	R. ft.	120
30	Do planking 4" thick	S. ft.	211
31	Zinc sheets for valley	Do	211
31A	Zinc down pipes	R. ft.	240
32	Tarring wood work and wood oiling	Sqr.	2000
33	Wrought Iron Trusses complete as per plan	Cwt.	61
34	Teakwood pannelled screen	S. ft.	166
35	Approach road	Lump sum	
36	Excavating well	Do	do
37	Dam allround the building	Do	do
38	Constructing latrine	Do	do
39	Do compound wall	Do	do

A. PUTTASAMAIYA
Executive Engineer.

MYSORE DIVISION.

It is hereby notified that a sum of Rs. 42-8-0 is due to Mr. K. Ramaswamiah, contractor, for constructing 2nd class Travellers Bungalow at Nanjangud, as per books of this office and if the amount is not claimed by the party within the period of three months from this date the said amount will be credited to Government.

V. V. KARVE,
Executive Engineer.